BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work : Maintainance and Emergency work in ward no 07 Byataraynapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	360.00	Earthwork and removal of silt or silt mixed with sand in slushy condition from canal bed including jack well disposing of the same in spoil bank or on the canal embankment in layers as directed etc., complete with initial lead upto 50m and all lifts		104.00	
2	360.00	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)		73.57	
3	140.00	Supply of Water through water tanker to immersion Tank		350.00	
4	400.00	HOM for pumping of 3.5 KL / Hr capacity pump (Page No.		50.00	
5	172.50	KSRRB 2-1.1 : Earthwork excavation in Ornary soil for leveling and Lowring the ground manually (other than foundation of Buildings culverts road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not		156.88	
6	14.50	Supplying and Spreading Stonedust for the Exsisting surface to		750.00	
7	14.40	Providing and Fixing flex board and caution boards for the		200.00	
8	750.00	Hire Charges for Armless Plastic Chairs		4.00	
9	120.00	Hire Charges for Steel Table of Size 6'x4'		40.00	
10	520.00	Hire charges for supplying and running circuit service main with		12.00	
11	11.00	Hire charges for Providing Mike system including amplyfire		1200.00	
12	300.00	Hire Charges for Shamiyana Side Wall of 8ft light (Size ss x 200		5.00	
13	3000.00	Hire charges for Shamiyana with necessary Bamo Poles Erection		15.00	
14	750.00	Hire charges for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining		10.00	
15	128.00	Hire charges for Flood lighting Arrangements for the stage and existing Immersion Tank during night time		285.00	
16	4500.00	Hire charges for Shamiyana with necessary Bamboo Poles		14.00	
17	7200.00	Hire Charges for Shamiyana Side Wall of 9ft light (Size 8 x 15 Ft		5.00	
18	375.00	Engaging unskilled heavy Mazdoor labour for Guarding and for helping the public to immersion tank Ganesh Idols and to safe		243.55	
19	36.00	Hire charges for Providing Flood lights for the stage		285.00	
20	120.00	1321 Hire Charges of 100KVA Generator including opertator,		630.00	
21	135.00	Hire charges for Providing Flood lights for the Existing Immersion		285.00	
22	360.00	Earthwork and removal of silt or silt mixed with sand in slushy condition from canal bed including jack well disposing of the		104.00	
23	360.00	Lead for Disposal of Debris shall be payable at carriage rates by		73.57	

24	68.00	Supply of Water through water tanker to immersion Tank		350.00	
25	**90.72**	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom		192.24	
26	**15.12**	KSRB 4-1.3: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete		5070.60	
27	**40.32**	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials,		4135.32	
28	**58.72**	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons.		244.08	
29	**44.42**	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing		6332.04	
30	**3.17**	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with		69805.80	
31	**33.60**	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.112.I.No. 15.3) SR-2015-16		99.36	

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

21/12